BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of work: Construcion of Division Office building in ward no. 8, Kodigehalli sub division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2.02	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications. - RCC grade M20 and above	cum	937.04	
2	9.88	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications. - Dismantling brick work in cement morta	cum	222.60	
3	43.48	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications	cum	6058.96	
4	6.93	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24 kg with 12mm and downsize graded granie metal coarse aggregaes @ 0.051 cum and fine aggregates @ 0.034 cum, with super plastisiser @ 0.225 lts, machine mixed, well compacted for plain chajja of 7.5 cm average thickness, upto ground floor level, including cost of all materials, laobur, HOM of machinery, finishing curing complete as per specifications	cum	460.04	
5	4.35	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	Tonne	77006.88	
6	414.02	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications.	sqm	561.80	

Exe.Engr.
Btp. Dn.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	21.62	KSRB 6-2.3 Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	cum	6297.46	

R.V. Subba Reddy
Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

ಕರಡು ಟೆಂಡರ್ ಪರಿಶೀಲನೆ
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ..... ನಿಲ್
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92